| D-205-B NOZZLE STREAM REACH & REACH @ HEIGHT | | | | | |
|--|-------------------|--------------------|--|--------------------------------------|------------|
| FLOW RATING | STREAM PATTERN | DISCHARGE ANGLE | MAX HORIZONTAL REACH AT GROUND LEVEL | MAX VERTICAL AT MAX HORIZONTAL | |
| | | | | VERTICAL | HORIZONTAL |
| 250 GPM @ 100 PSI | SS | 32` | 103 | 26 | 67 |
| | SS | 55` | 78 | 39 | 51 |
| | SS | 75` | 46 | 59 | 33 |
| | NARROW FOG | 32` | 57 | 14 | 37 |
| | NARROW FOG | 55` | 43 | 22 | 28 |
| | NARROW FOG | 75` | 25 | 33 | 18 |
| | WIDE FOG | 32` | 36 | 9 | 23 |
| | WIDE FOG | 55` | 27 | 14 | 18 |
| | WIDE FOG | 75` | 16 | 21 | 12 |

NOTE: All data provided in this chart is an Engineering Estimate. Actual results will vary based on environmental and system conditions. All systems must be tested after installation to verify installed water delivery reach and loft.